

**Tree Inventory and Preservation Plan Report
Milton Porta Lands
Milton, ON**

prepared for

**Studio TLA
20 Champlain Boulevard
North York, ON M3H 2Z1**

prepared by



146 Lakeshore Road West
PO Box 1267 Lakeshore W PO
Oakville ON L6K 0B3
t: 289.837.1871
e: consult@kuntzforestry.ca

28 April 2020
Revised: 04 May 2020, 19 June 2020, 05 August 2020,
10 August 2020, 06 April 2021

KUNTZ FORESTRY CONSULTING INC Project P2375

Introduction

Kuntz Forestry Consulting Inc. was retained by Studio TLA to complete a Tree Inventory and Preservation Plan report in support of a development application for four properties located at 8802 Boston Church Road, 8830 Boston Church Road, 8880 Boston Church Road, and 8350 Esquesing Line. The first three properties are located on the southwest corner of the Boston Church Road and No. 5 Sideroad intersection and the fourth property is located on the northeast corner of the Boston Church Road and James Snow Parkway North intersection in Milton, ON. The properties are located within a residential and agricultural area.

The work plan for the study included the following:

- Prepare inventory of the tree resources over 10cm on and within six metres of the subject properties (excluding the existing woodlot) and trees of all sizes within the road right-of-way;
- Evaluate potential tree saving opportunities based on proposed development plans; and,
- Document the findings in a Tree Inventory and Preservation Plan Report.

Methodology

The tree inventory was conducted on 21 April 2020, 22 April 2020, 24 April 2020, and 05 August 2020. Trees measuring over 10cm DBH on and within six metres of the subject properties were identified in the tree inventory. Trees were located using the topographic survey provided, estimations made in the field, and a handheld GPS unit (Trimble GeoExplorer® Series) accurate to ± 1 metre. The dripline distance was used in the preservation planning analysis to determine if tree removal is required. Where development is proposed within a dripline, there is the potential to damage tree roots and tree removal may be required.

Tree resources were assessed utilizing the following parameters:

Tree # - tree number that corresponds to the inventory and Figures 1 – 9.

Species - common and botanical names provided in the inventory table.

DBH - diameter (centimetres) at breast height, measured at 1.4 m above the ground.

Condition - condition of tree considering trunk integrity, crown structure, crown vigour, and root zone environment. Condition ratings include poor (P), fair (F) and good (G).

Crown Dieback – Percentage of dead branches within the crown.

Drip Line - Crown radius; and

Comments – Any other relevant tree condition information.

Stand Tally Analysis

Where trees were situated in groups and their individual locations could not be deciphered, they were inventoried in tree polygons. Tree polygons are denoted with a "P" in front of the tree number. Trees within a tree polygon were inventoried using a 100% tally analysis by species, size class, and quality. On private property, trees with a DBH of 10cm or greater were included in the stand tally analysis. Within the City right-of-way, trees of all sizes were included in the stand tally analysis.

Trees were assessed for condition utilizing the following parameters:

Species: Common and botanical names provided in the inventory table;

Size Class (DBH): less than 10cm, 10 – 24cm, 26 – 36cm, 38 – 48cm, 50 cm and over;

Quality Class: Acceptable Growing Stock (AGS), Unacceptable Growing Stock (UGS)

Trees classified as AGS are trees with no major defects in the bole and exhibit a relatively good crown structure and vigour. Trees classified as UGS are trees with a major defect in the bole or exhibiting a relatively poor crown structure or vigour. Refer to Table 2 for the inventory of trees situated within polygons.

Trees included in the inventory were identified using the numbers 651 – 697, 1583 – 1682, 1678, and 1680 – 1702. Polygons (groups of trees) were identified with the prefix "P". Refer to Table 1 and Table 2 for the complete tree inventory. The results of the evaluation are provided below.

Existing Site Conditions

The subject properties are comprised of agricultural lands with residential houses. A CN railway corridor borders the west side of the property at 8880 Boston Church Road in the north to south direction. A Hydro corridor borders 8350 Esquesing Line to the south in the west to east direction. There is an existing woodland that runs along the northern border of the property at 8350 Esquesing Line. Both sites are bordered by No. 5 Sideroad to the north, Esquesing Line to the east, and James Snow Parkway North to the south.

The tree inventory documented a total of 142 trees and 19 tree polygons situated on and within six metres of the development area. Trees included in the inventory were comprised of Apple species (*Malus* spp.), Black Walnut (*Juglans nigra*), Sugar Maple (*Acer saccharum*), Norway Maple (*Acer platanoides*), White Ash (*Fraxinus americana*), Bur Oak (*Quercus macrocarpa*), White Elm (*Ulmus americana*), Little-leaf Linden (*Tilia cordata*), Weeping Willow (*Salix babylonica*), Horsechestnut (*Aesculus hippocastanum*), Austrian Pine (*Pinus nigra*), Red Maple (*Acer rubrum*), Yew species (*Taxus* spp.), Scots Pine (*Pinus Sylvestris*), Blue Spruce (*Picea pungens*), Umbrella Catalpa (*Catalpa bignoniifolia* 'Nana'), Eastern White Cedar (*Thuja occidentalis*), White Spruce (*Picea glauca*), Silver Maple (*Acer saccharinum*), White Birch (*Betula papyrifera*), Trembling Aspen (*Populus tremuloides*), Tamarack (*Larix laricina*), White Pine (*Pinus strobus*), Norway Spruce (*Picea abies*), Green Ash (*Fraxinus pennsylvanica*), Black Locust (*Robinia pseudoacacia*), Manitoba Maple (*Acer negundo*), Shagbark Hickory (*Carya ovata*), Cherry species (*Prunus* spp.), Black Cherry (*Prunus serotina*), Poplar species (*Populus* spp.), Pear species (*Pyrus* spp.), Willow species (*Salix* spp.), Basswood (*Tilia americana*), and Honey Locust cultivar (*Gleditsia triacanthos* 'inermis'). Tree polygons inventoried on the subject property do not constitute as woodlands per the Halton Tree Bylaw 121-05. Refer to Table 1 and Table 2 for the complete inventory and Figures 1 – 9 for tree locations.

Proposed Development

The proposed development includes the construction of a business park with multiple buildings, two storm water management ponds, roads, parking lots, and new water channels. The development will also include the widening of Boston Church Road.

There are two holdout properties (8820 Boston Church Road and 8480 Esquesing Line) located in the middle of the development. The existing house at 8350 Esquesing Line is proposed to be moved southeast of the storm water management pond on James Snow Parkway, as this is a designated Heritage Home. The development is part of a larger project that is proposed for this area in Milton.

Discussion

The following sections provide a discussion and analysis of development impacts, tree removal requirements, and tree preservation relative to the proposed development and existing conditions.

Development Impacts / Tree Removal

The removal of 123 trees and 16 tree polygons will be required to accommodate the proposed development. Trees P1584, 1619 – 1623, and 1687 – 1690 have trunks that conflict directly with the proposed buildings. Trees P1585, 1634, and 1665 – 1672 have trunks that conflict directly with the proposed trailer locations. Trees P1614, P1615 and P1624 – 1629 conflict with the proposed Storm Water Management Pond. Trees 662 – 664, P1616 – 1618, 1630, 1632, P1662, 1678, 1680, 1681, 1685, 1686, 1691, 1692, and 1695 have trunks that conflict directly with the proposed roads and parking lots on site. Trees P661, 1683, 1684, 1693, and 1694 are located close to the proposed parking lots such that their roots and / or crowns would be impacted by construction. Trees 651 – 653, P666 – 670, 674, 676 – 679, 696, P1638 – 1661, and 1696 – 1702 have trunks that conflict with the proposed road widening along Boston Church Road. Tree 671 is located close to the proposed road widening along Boston Church Road such that its roots and / or crown would be impacted by construction. Trees 672, 673, and 686 – 692 are located close to the existing houses such that their roots and / or crowns would be impacted by demolition. Tree 697 is located close to the existing driveway such that its roots and / or crown would be impacted by driveway demolition. Trees 1663 and 1664 conflict with the proposed channel construction. P1631 and 1633 conflict with both the proposed buildings and parking lots. Trees 654 – 660, 681, 683 – 685, 693, 694, 1568 – 1588, and the eastern portion of P1605 conflict with the proposed site clearing. The western portion of P1605 conflicts with the proposed channel construction.

Trees 665, 667 – 670, 675, 680, 682, 689, 695, 1583, 1597, 1599, 1611, 1621 – 1623, 1630, 1637, 1639, 1643, 1649, 1654, 1660, 1661, 1667, 1670, 1672, 1682, 1690, 1695 – 1697, and 1699 – 1702 are in poor or hazardous condition and their removal is advised regardless of the site plan. Tree 675 is located on the property boundary and written permission from its shared owner will be required prior to its removal.

Tree Preservation

The preservation of the remaining 19 trees, three tree polygons and the existing woodlot will be possible with the use of appropriate tree protection measures as indicated on Figure 1. Tree protection measures must be implemented prior to the proposed work to ensure tree resources designated for retention are not impacted by the proposed development. Tree preservation fencing for the existing woodlot should be placed at a distance of three metres north of the proposed development in order to provide space for grading and construction. Tree preservation fencing must be placed at *minimally* outside the dripline of all trees within the existing woodlot. Trees prescribed for retention within

the City right-of-way are subject to future road widening plans, future regrading plans, and future site plans, which may impact their retention suitability. Refer to Figures 1 – 9 for the location of required tree preservation fencing and general Tree Protection Plan Notes. Refer to Appendix A for tree preservation fencing details.

Summary and Recommendations

Kuntz Forestry Consulting Inc. was retained by Studio TLA to complete a Tree Inventory and Preservation Plan in support of a development application for the Milton Porta Lands in Milton, Ontario. A tree inventory was conducted and reviewed in the context of the proposed site plan.

The findings of the study indicate a total of 142 trees and 19 polygon features on and within six metres of the proposed development area and within the City right-of-way. The removal of 123 trees and 16 polygon features is required to accommodate the proposed development. The remaining trees can be saved provided proper tree protection is installed as per Figures 1 – 9.

The following recommendations are suggested to minimize impacts to trees identified for preservation. Refer to Figures 1 – 9 for tree protection fencing locations and general Tree Protection Plan Notes.

- Tree protection barriers and fencing should be erected at locations as prescribed on Figures 1 – 9. All tree protection measures should follow the guidelines as set out in the tree preservation plan notes and the tree preservation fencing detail.
- No construction activity including surface treatments, excavations of any kind, storage of materials or vehicles, unless specifically outlined above, is permitted within the area identified on Figures 1 – 9 as a tree protection zone (TPZ) at any time during or after construction.
- Branches and roots that extend beyond prescribed tree protection zones that require pruning must be pruned by a qualified Arborist or other tree professional. All pruning of tree roots and branches must be in accordance with Good Arboricultural Standards.
- Site visits, pre, during and post construction is recommended by either a certified consulting arborist (I.S.A.) or registered professional forester (R.P.F.) to ensure proper utilization of tree protection barriers. Trees should also be inspected for damage incurred during construction to ensure appropriate pruning or other measures are implemented.

Respectfully Submitted,

Kuntz Forestry Consulting Inc.

Kimberly Dowell

Kimberly Dowell, Urban Forestry Specialist
Master of Forest Conservation, ISA Certified Arborist #PN-8858A
Email: kim.dowell@kuntzforestry.ca

Limitations of Assessment

Only the tree(s) identified in this report were included in the inventory. The assessment of the trees presented in this report has been made using accepted arboricultural techniques. These may include a visual examination taken from the ground of all the above-ground parts of the tree for structural defects, scars, external indications of decay such as fungal fruiting bodies, evidence of attack by insects, discoloured foliage, the condition of any visible root structures, the degree of lean (if any), the general condition of the trees and the identification of potentially hazardous trees or recommendations for removal (if applicable). Where trees could not be directly accessed (ie. due to obstructions, and/or on neighbouring properties), trees were assessed as accurately as possible from nearby vantage points.

Locations of trees provided in the report are determined as accurately as possible based on the best information available. If official survey information is not provided, tree location in the report may not be exact. In this case, if trees occur on or near property boundaries, an official site survey may be required to determine ownership utilizing specialized survey protocol to gain precise location.

Furthermore, recommendations made in this report are based on the site plans that have been provided at the time of reporting. These recommendations may no longer be applicable should changes be made to the site plan and/or grading, servicing, or landscaping plans following report submission.

Notwithstanding the recommendations and conclusions made in this report, it must be recognized that trees are living organisms, and their health and vigor constantly change over time. They are not immune to changes in site conditions or seasonal variations in the weather conditions. Any tree will fail if the forces applied to the tree exceed the strength of the tree or its parts.

Although every effort has been made to ensure that this assessment is reasonably accurate, the trees should be re-assessed periodically. The assessment presented in this report is valid at the time of inspection.

Appendix A. Tree Protection Fencing Guidelines




Table 1. Tree Inventory

Location: Milton Porta Lands, Milton

Date: 21 April 2020, 22 April 2020, 24 April 2020, 05 August 2020

Surveyors: KD

Tree#	Common Name	Scientific Name	DBH	TI	CS	CV	CDB	DL	Comments	Action
651	Cherry species	<i>Prunus</i> spp.	7, 5, 5, 5	F	F	F-G		1.5	Co-dominant stems at base, stem wound (M)	Remove
P652	Eastern White Cedar	<i>Thuja occidentalis</i>	5 - 15	F-G	F	F-G		2	Asymmetrical crown (H), multi-stem at base, one stem dead, epicormic branching (H)	Remove
653	Apple species	<i>Malus</i> spp.	35, 30, 30	F	P-F	P-F		5	8 trees, some multi-stem at base, asymmetrical crown (M)	Remove
654	Honey Locust (cultivar)	<i>Gleditsia triacanthos 'inermis' cv.</i>	39, 24, 16	F-G	F	F	10	4	Pruning wounds (M), multi-stem at 1 metre, deadwood (L), epicormic branching (M)	Remove
655	Silver Maple	<i>Acer saccharinum</i>	51	F-G	F	P-F		6	Co-dominant stems at 1.5 metres, epicormic branching (H), deadwood (L)	Remove
656	Silver Maple	<i>Acer saccharinum</i>	90	F-G	F	F-G		8	Multi-stem at 1.5 metres, epicormic branching (M)	Remove
657	Basswood	<i>Tilia americana</i>	27	F	P-F	P-F		4	Asymmetrical crown (H), lost leader, bow (H) from lost leader, coppice growth (M), epicormic branching (M) pruning wounds (M)	Remove
658	Poplar species	<i>Populus</i> spp.	11	G	G	F-G		1		Remove
659	Poplar species	<i>Populus</i> spp.	12, 10	G	F	F-G	5	1	Co-dominant stems at base, epicormic branching (M)	Remove
660	Poplar species	<i>Populus</i> spp.	14, 12	G	F	F		1.5	Co-dominant stems at base, epicormic branching (H)	Remove
P661	Eastern White Cedar	<i>Thuja occidentalis</i>	5 - 25	F-G	F-G	F-G		2	10 trees, many with sweep (M), some multi-stem	Remove
662	Scots Pine	<i>Pinus sylvestris</i>	31	F-G	F-G	F-G		2	Sweep (L), crooks (L), asymmetrical crown (L)	Remove
663	Scots Pine	<i>Pinus sylvestris</i>	32	F-G	F-G	G		3	Pruning wounds (L), sweep (L)	Remove
664	Scots Pine	<i>Pinus sylvestris</i>	31, 22	F-G	F	G		3	Co-dominant stems at base, crook (H), sweep (L)	Remove
665	Eastern White Cedar	<i>Thuja occidentalis</i>	33	P	P-F	G		1.5	Crack (H) at union, co-dominant stems at 2 metres, pruning wounds (M), lean (L)	Remove (Condition)
P666	Eastern White Cedar	<i>Thuja occidentalis</i>	10 - 30	F	F	F		2.5	16 trees, some with lean (M), many multi-stem, some with stem wounds (M), some are declining	Remove
667	Green Ash	<i>Fraxinus pennsylvanica</i>	-	-	-	-	-	-	Dead	Remove (Condition)
668	Green Ash	<i>Fraxinus pennsylvanica</i>	5 - 15	P	P	P	25	2	EAB present, bark peeling, epicormic branching (H), top-down dieback	Remove (Condition)
669	White Ash	<i>Fraxinus americana</i>	5 - 20	P	P	P	50	2	Bark peeling, EAB present, epicormic branching (H)	Remove (Condition)
670	Green Ash	<i>Fraxinus pennsylvanica</i>	10, 5, 3	P	P	P-F		1	Co-dominant stems at base, epicormic branching (M), EAB present	Remove (Condition)
671	White Birch	<i>Betula papyrifera</i>	17, 17, 17	F-G	F	F-G		3	Multi-stem at base, stem wound (H) on one stem, pruning wounds (L), dw (L)	Remove
672	Honey Locust (cultivar)	<i>Gleditsia triacanthos 'inermis' cv.</i>	46, 40	F-G	F	F		7	Co-dominant stems at 1 metre, pruning wounds (M), deadwood (L), epicormic branching (L), broken branches (L)	Remove
673	Eastern White Cedar	<i>Thuja occidentalis</i>	30, 24	F-G	F	G		1.5	Co-dominant stems at 1 metre, pruning wounds (M)	Remove
674	Trembling Aspen	<i>Populus tremuloides</i>	1 - 5	G	F	G		1	Multi-stem at base	Remove
675	Manitoba Maple	<i>Acer negundo</i>	50	P	P-F	P-F		5	Stem wounds (H), epicormic branching (H), co-dominant stems at 1 metre deadwood (M), broken branches (M)	Remove (Condition)
676	White Spruce	<i>Picea glauca</i>	23	G	G	G		2	Epicormic branching (L), pruning wounds (M)	Remove
677	White Pine	<i>Pinus strobus</i>	28	G	F-G	G		3	Crook (M) in crown, pruning wounds (L)	Remove

678	White Birch	<i>Betula papyrifera</i>	22	G	F-G	F-G		5	Sweep (L), deadwood (L), asymmetrical crown (L)	Remove
679	Silver Maple	<i>Acer saccharinum</i>	71	F	F	P	20	7	Co-dominant stems at 1.5 metres, epicormic branching (H), deadwood (M), top-down dieback	Remove
680	Tamarack	<i>Larix laricina</i>	14	F	P	P	15	2.5	Asymmetrical crown (H), epicormic branching (M), top-down dieback	Remove (Condition)
681	White Pine	<i>Pinus strobus</i>	35	G	F-G	G		7	Asymmetrical crown (M), pruning wounds (L)	Remove
682	Silver Maple	<i>Acer saccharinum</i>	75	F-G	F-G	P-F	20	6	Top-down dieback, multi-stem at 2 metres, deadwood (H), epicormic branching (H)	Remove (Condition)
683	Norway Spruce	<i>Picea abies</i>	24	G	F-G	G		3	Asymmetrical crown (M)	Remove
684	Norway Maple	<i>Acer platanoides</i>	27	G	F-G	G		4		Remove
685	White Pine	<i>Pinus strobus</i>	35	G	F-G	G		6	Asymmetrical crown (M)	Remove
686	Blue Spruce	<i>Picea pungens</i>	46	G	F-G	G		4	Asymmetrical crown (M)	Remove
687	White Spruce	<i>Picea glauca</i>	42	G	G	G		3		Remove
688	Tamarack	<i>Larix laricina</i>	24	G	G	G		3	Asymmetrical crown (L)	Remove
689	Green Ash	<i>Fraxinus pennsylvanica</i>	-	-	-	-	-	-	Dead	Remove (Condition)
P690	Green Ash	<i>Fraxinus pennsylvanica</i>	10	P	F	P	-	1.5	1 tree	Remove
	Eastern White Cedar	<i>Thuja occidentalis</i>	5 - 20	F	F	F	-	1.5	12 trees, some multi-stem, some with sweep (M), some with lean (L)	
691	White Pine	<i>Pinus strobus</i>	39	G	F-G	G		7	Sweep (M)	Remove
692	White Pine	<i>Pinus strobus</i>	41	G	F-G	G		7	Asymmetrical crown (M), pruning wounds (L)	Remove
693	Willow species	<i>Salix</i> spp.	5 - 10	F	F	F-G		3	Multi-stem at base, deadwood (L)	Remove
694	Willow species	<i>Salix</i> spp.	5 - 15	F-G	F	F-G		3	Multi-stem at base, deadwood (L), pruning wounds (L), lean (L), asymmetrical crown (M)	Remove
695	Cherry species	<i>Prunus</i> spp.	5 - 15	P	P-F	F	5	4	Trunk decay (M), multi-stem at 1.25 metres, deadwood (L), epicormic branching (L)	Remove (Condition)
696	White Pine	<i>Pinus strobus</i>	49	F	F	G		7	Lean (M)	Remove
697	White Pine	<i>Pinus strobus</i>	34	G	G	F-G	10	4	Asymmetrical crown (L)	Remove
1583	Green Ash	<i>Fraxinus americana</i>	30	P	P	P		3.5	One stem previously pruned at 1 metre, EAB present, bark peeling	Remove (Condition)
P1584	Refer to Table 2									Remove
P1585	Refer to Table 2									Remove
1586	Black Walnut	<i>Juglans nigra</i>	18, 15	F	F	P-F		2.5	Co-dominant stems at 0.5 metres, broken branches (L), stem wound (M) from 0.75 to 1.5 metres	Remove
1587	Sugar Maple	<i>Acer saccharum</i>	14	G	G	G		1.5		Remove
1588	Sugar Maple	<i>Acer saccharum</i>	13	G	G	F-G		1.5		Remove
1589	Sugar Maple	<i>Acer saccharum</i>	~10, ~9, ~8	G	F	G		1.5	Multi-stem at base	Retain
1590	Sugar Maple	<i>Acer saccharum</i>	~45, ~40	P-F	F	F-G		4	Co-dominant stems at base, one stem pruned at 3 metres, broken branches (M), cavities (M)	Retain
1591	Norway Maple	<i>Acer platanoides</i>	~15	G	G	G		2		Retain
1592	Norway Maple	<i>Acer platanoides</i>	~40	F-G	F-G	G		4.5		Retain
1593	Sugar Maple	<i>Acer saccharum</i>	~20	G	G	G		3		Retain
1594	Norway Maple	<i>Acer platanoides</i>	~45	P	P-F	F		3.5	Multiple cavities (H), lost leader, epicormic branching (M)	Retain
1595	Norway Maple	<i>Acer platanoides</i>	~18	G	G	G		3	Lean (L)	Retain

1596	Sugar Maple	<i>Acer saccharum</i>	~60	P-F	P-F	P-F		6	Asymmetrical crown (H), co-dominant stems at 2 metres, one stem pruned at 4 metres, epicormic branching (H), cavities (M)	Retain
1597	Sugar Maple	<i>Acer saccharum</i>	~55	P	P	P-F		5.5	Cavities (H), stems split at union, multi-stem at 2 metres, broken branches (H), epicormic branching (H)	Remove (Condition)
1598	Sugar Maple	<i>Acer saccharum</i>	~60	F-G	F-G	F		6	Epicormic branching (M), co-dominant stems at 4 metres	Retain
1599	White Ash	<i>Fraxinus americana</i>	~35	P-F	P-F	P	50	5	Top-down dieback	Remove (Condition)
1600	White Ash	<i>Fraxinus americana</i>	~13	F-G	F-G	F-G		3		Retain
P1601	Green Ash	<i>Fraxinus pennsylvanica</i>	~15	F	F	F		1	2 trees	Retain
	Bur Oak	<i>Quercus macrocarpa</i>	~10	G	G	G			1 tree	
1602	White Elm	<i>Ulmus americana</i>	~75	F-G	F	F-G		7	Multi-stem at 2.5 metres, broken branches (L), epicormic branching (M)	Retain
1603	Sugar Maple	<i>Acer saccharum</i>	~65	G	F-G	G		7		Retain
1604	Norway Maple	<i>Acer platanoides</i>	16	G	G	G		2		Retain
P1605	Refer to Table 2									Remove
P1606	Refer to Table 2									Retain
P1607	Refer to Table 2									Retain
1608	White Elm	<i>Ulmus americana</i>	11	F-G	F	F		2	Epicormic branching (M)	Retain
1609	Black Walnut	<i>Juglans nigra</i>	14, 12	F-G	F	G		2.5	Co-dominant stems at 0.75 metres, included bark (L)	Retain
1610	Black Walnut	<i>Juglans nigra</i>	14, 8, 8	F-G	F-G	G		2.5	Co-dominant stems at 0.5 metres, broken branches (L)	Retain
1611	Black Walnut	<i>Juglans nigra</i>	29	P	F	P-F		3	Stem wound (H) from base to 1 metre, bark peeling, broken branches (M)	Remove (Condition)
1612	Black Walnut	<i>Juglans nigra</i>	30	G	G	G		3.5	Broken branches (L)	Retain
1613	Black Walnut	<i>Juglans nigra</i>	31	F-G	G	G		3.5	Broken branches (L)	Retain
P1614	Refer to Table 2									Remove
P1615	Refer to Table 2									Remove
P1616	Refer to Table 2									Remove
1617	White Oak	<i>Quercus alba</i>	35	F-G	G	G		4		Remove
1618	Little-leaf Linden	<i>Tilia cordata</i>	18	G	G	G		2.5	Included bark (L)	Remove
1619	Little-leaf Linden	<i>Tilia cordata</i>	19	G	F-G	G		3		Remove
1620	Little-leaf Linden	<i>Tilia cordata</i>	15	G	G	G		2.5	Included bark (L)	Remove
1621	Weeping Willow	<i>Salix babylonica</i>	~50	P	F	P-F		6	Lean (L), stem wound (H) at base, vine competition (H), deadwood (M), epicormic branching (H), broken branches (M)	Remove (Condition)
1622	Weeping Willow	<i>Salix babylonica</i>	20	P	F	P-F		5	Epicormic branching (H), stem wound (H) at base, cavity (H) at base	Remove (Condition)
1623	Weeping Willow	<i>Salix babylonica</i>	~40, ~35, ~25	P-F	P-F	P-F		6	Broken branches (H), epicormic branching (H), multi-stem at base	Remove (Condition)
P1624	Refer to Table 2									Remove
1625	Willow species	<i>Salix spp.</i>	98	F	F	P-F		8	Epicormic branching (H), coppice growth (M), broken branches (L), multi-stem at 1.5 metres	Remove
1626	Willow species	<i>Salix spp.</i>	59	F	F	F		7	Epicormic branching (H), coppice growth (M), broken branches (L), co-dominant stems at 2 metres	Remove
1627	Bur Oak	<i>Quercus macrocarpa</i>	71	G	F-G	F		7	Epicormic branching (M)	Remove
1628	Bur Oak	<i>Quercus macrocarpa</i>	~53	F	G	F		7	Included fence, epicormic branching (H)	Remove

1629	Bur Oak	<i>Quercus macrocarpa</i>	~75	F	F	F	9		Included fence, pruning wounds (M), asymmetrical crown (M), epicormic branching (H)	Remove
1630	Bur Oak	<i>Quercus macrocarpa</i>	~90	P	P-F	P	10	40	Stem wound (H) from base to 4 metres, cavity (H) at base, epicormic branching (H), deadwood (H)	Remove (Condition)
P1631	Refer to Table 2									Remove
1632	White Ash	<i>Fraxinus americana</i>	14, 6, 5, 5	F	F	F		2	EAB present, epicormic branching (M), vine competition (H)	Remove
P1633	Refer to Table 2									Remove
1634	Bur Oak	<i>Quercus macrocarpa</i>	82	G	F-G	F		8	Epicormic branching (M)	Remove
P1635	Refer to Table 2									Remove
1636	Bur Oak	<i>Quercus macrocarpa</i>	21	G	G	F-G		3	Epicormic branching (M)	Retain
1637	Horsechestnut	<i>Aesculus hippocastanum</i>	72, 22	P	P	P-F	60	6	Broken branches (H), cavity (H) at 2 metres, epicormic branching (H), deadwood (M), pruning wounds (M)	Remove (Condition)
P1638	Refer to Table 2									Remove
1639	White Ash	<i>Fraxinus americana</i>	90	P	P	P			Dead	Remove (Condition)
1640	Sugar Maple	<i>Acer saccharum</i>	50	P-F	G	F		6	Cavities (M), included fence, epicormic branching (M)	Remove
1641	Basswood	<i>Tilia americana</i>	23	G	F-G	G		3.5	One stem previously pruned at base	Remove
1642	Basswood	<i>Tilia americana</i>	24, 15	F-G	F	G		3.5	One stem previously pruned at base, co-dominant stems at base	Remove
1643	Dead	-	-	-	-	-	-	-	-	Remove (Condition)
1644	Basswood	<i>Tilia americana</i>	18	G	G	F-G		3		Remove
1645	Basswood	<i>Tilia americana</i>	21, 13	F-G	F	F-G		3	Co-dominant stems at base	Remove
1646	Basswood	<i>Tilia americana</i>	14	G	G	F-G		1.5		Remove
1647	Basswood	<i>Tilia americana</i>	13	G	G	G		1.5		Remove
1648	Basswood	<i>Tilia americana</i>	23	G	F-G	G		4		Remove
1649	Basswood	<i>Tilia americana</i>	10 - 40 (Average: 25)	P	P	P-F		5	Multi-stem at base, multiple previous stem failures, cavities (H), decay, deadwood (M)	Remove (Condition)
1650	Basswood	<i>Tilia americana</i>	12	G	G	G		1		Remove
1651	Basswood	<i>Tilia americana</i>	13	G	G	G		1.5		Remove
1652	Basswood	<i>Tilia americana</i>	11	G	G	G		1.5		Remove
1653	Basswood	<i>Tilia americana</i>	17	G	F	F-G		2	Suppressed	Remove
1654	White Ash	<i>Fraxinus americana</i>	~100	P-F	F	P		9	Epicormic branching (H), EAB present	Remove (Condition)
1655	Basswood	<i>Tilia americana</i>	15	F	G	F		1.5		Remove
1656	Basswood	<i>Tilia americana</i>	18, 21	F-G	F	G		3.5	Bow (L)	Remove
1657	Basswood	<i>Tilia americana</i>	19	F-G	F-G	F-G		3	Lean (L), suppressed	Remove
1658	White Ash	<i>Fraxinus americana</i>	15, 9	F	F	F		2	Co-dominant stems at base	Remove
1659	Sugar Maple	<i>Acer saccharum</i>	54	F-G	G	F-G		7	Deadwood (M), broken branches (L), epicormic branching (M), included fence	Remove
1660	White Ash	<i>Fraxinus americana</i>	~80					0	Dead	Remove (Condition)
1661	Sugar Maple	<i>Acer saccharum</i>	~50	P	P	F		6	Included fence, cavity (H) from base to 3 metres, hazard	Remove (Condition)
P1662	White Elm	<i>Ulmus americana</i>	3 - 12	G	G	G	1.5		4 trees, 3 trees under 10cm DBH, 1 tree 12 cm DBH	Remove
1663	Green Ash	<i>Fraxinus pennsylvanica</i>	11	F	G	F		1.5		Remove

1664	Apple species	<i>Malus</i> spp.	30	F	FP	F		3.5	Deadwood (M), included bark (H)	Remove
1665	Apple species	<i>Malus</i> spp.	1 - 15 (Average: 9)	P-F	P-F	P-F		3	Multi-stem at base, deadwood (M), included bark	Remove
1666	Apple species	<i>Malus</i> spp.	10 - 25 (Average: 15)	F	F	F		3	Multi-stem at base, epicormic branching (M)	Remove
1667	Pear species	<i>Pyrus</i> spp.	10 - 20 (Average: 12)	P-F	P-F	P		3.5	deadwood (H), multi-stem at base, epicormic branching (H)	Remove (Condition)
1668	Apple species	<i>Malus</i> spp.	10 - 20 (Average: 18)	P-F	P-F	P-F		3	Epicormic branching (H), multi-stem at base, deadwood (M)	Remove
1669	Apple species	<i>Malus</i> spp.	17	F-G	F-G	F		3	Epicormic branching (M), lean (L)	Remove
1670	Green Ash	<i>Fraxinus pennsylvanica</i>	11, 10, 8, 6	P	P	P-F		2	Bark peeling, vine competition (H), multi-stem at base, EAB present	Remove (Condition)
1671	Apple species	<i>Malus</i> spp.	15 - 40 (Average: 30)	P-F	P-F	P-F		4.5	Included bark (H), multi-stem at base, epicormic branching (H), deadwood (M)	Remove
1672	White Ash	<i>Fraxinus americana</i>	24	P	P	P			Dead	Remove (Condition)
1678	Silver Maple	<i>Acer saccharinum</i>	39	F-G	F	G	4.5		Included bark (H), co-dominant stems at 0.25 metres	Remove
1680	Red Maple	<i>Acer rubrum</i>	17	F-G	G	G	2			Remove
1681	Silver Maple	<i>Acer saccharinum</i>	5 - 15 (Average: 11)	G	F	G	2.5			Remove
1682	Poplar species	<i>Populus</i> spp.	15 - 40 (Average: 30)	P	P	P	5	80	Deadwood (H), multi-stem at base	Remove (Condition)
1683	White Elm	<i>Ulmus americana</i>	~25, ~9, ~7	F	F-G	F	3		Timber debris in root zone, co-dominant stems at 0.5 metres	Remove
1684	Austrian Pine	<i>Pinus nigra</i>	22	F-G	G	G	2.5		Pruning wounds (M)	Remove
1685	Honey Locust (cultivar)	<i>Gleditsia triacanthos</i> 'inermis' cv.	26, 13	F-G	F-G	F-G	3.5		Broken branches (L)	Remove
1686	Yew species	<i>Taxus</i> spp.	1 - 10	F-G	F	G	1.5			Remove
1687	Apple species	<i>Malus</i> spp.	~40	F-G	F-G	F	2.5		Sweep (L), pruning wounds (M), epicormic branching (M)	Remove
1688	Willow species	<i>Salix</i> spp.	1 - 15 (Average: 12)	P-F	P-F	P-F		2	Multi-stem at base, deadwood (M), included bark	Remove
1689	Silver Maple	<i>Acer saccharinum</i>	8 - 35 (Average: 17)	F-G	F	F-G		5	Multi-stem at base, included bark (M), epicormic branching (L)	Remove
1690	White Ash	<i>Fraxinus americana</i>	20	P	G	P	2.5		EAB present, declining	Remove (Condition)
1691	Austrian Pine	<i>Pinus nigra</i>	31	G	F-G	G	3		Pruning wounds (M), sweep (L)	Remove
1692	Blue Spruce	<i>Picea pungens</i>	36	F-G	F	F-G		4	Epicormic branching (L), crook (H) from topping at 5 metres, pruning wounds (M)	Remove
1693	Silver Maple	<i>Acer saccharinum</i>	52	F-G	F	F-G	6		Multi-stem at 2 metres, broken branches (L), epicormic branching (M)	Remove
1694	Umbrella Catalpa	<i>Catalpa bugnei</i> 'Nana'	15	P	F	P		1.5	Cavity (H) at 1 metre, epicormic branching (H), pruning wounds (M), stem wound (H) at 1 metre	Remove
1695	Basswood	<i>Tilia americana</i>	5 - 12 (Average: 11)	P	P	P		2	Multi-stem at base, deadwood (H), declining	Remove (Condition)
1696	Green Ash	<i>Fraxinus pennsylvanica</i>	21, 14	P	F	P-F		3	Bark peeling, EAB present	Remove (Condition)
1697	Green Ash	<i>Fraxinus pennsylvanica</i>	17, 12	P	F	P-F		2	Bark peeling, EAB present	Remove (Condition)
1698	Sugar Maple	<i>Acer saccharum</i>	~50	F	G	F		8	Included fence, broken branches (L), epicormic branching (H)	Remove

1697	Green Ash	<i>Fraxinus pennsylvanica</i>	17, 12	P	F	P-F		2	Bark peeling, EAB present	Remove (Condition)
1698	Sugar Maple	<i>Acer saccharum</i>	~50	F	G	F		8	Included fence, broken branches (L), epicormic branching (H)	Remove
1699	White Ash	<i>Fraxinus americana</i>	~100	F	F	P-F		8	EAB present	Remove (Condition)
1700	Green Ash	<i>Fraxinus pennsylvanica</i>	~100	P	F	P		8	EAB present, bark peeling, epicormic branching (H), deadwood (M)	Remove (Condition)
1701	White Ash	<i>Fraxinus americana</i>	21	P	G	P		2.5	Bark peeling, EAB present	Remove (Condition)
1702	White Ash	<i>Fraxinus americana</i>	~90	P	F	P		7	EAB present, bark peeling, broken branches (H), deadwood (H)	Remove (Condition)

Codes		
DBH	Diameter at Breast Height	(cm)
TI	Trunk Integrity	(G, F, P)
CS	Crown Structure	(G, F, P)
CV	Crown Vigor	(G, F, P)
CDB	Crown Dieback	%
DL	Dripline	(m)
P = poor, F = fair, G = good, ~ = estimate, (VL) = very light, (L) = light, (M) = moderate, (H) = heavy		

Table 2. Stand Tally Analysis

P1584

Tree Size Class > Species	Polewood (10 - 24 cm DBH)		Small (26 - 36 cm DBH)		Medium (38 - 48 cm)		Large (50 cm +)		Total All Sizes	
	AGS	UGS	AGS	UGS	AGS	UGS	AGS	UGS	AGS	UGS
White Elm (<i>Ulmus americana</i>)	1	0	0	0	0	0	0	0	1	0
Bur Oak (<i>Quercus macrocarpa</i>)	98	21	34	2	15	1	8	1	155	25
White Ash (<i>Fraxinus americana</i>)	0	0	0	0	0	0	0	1	0	1
Green Ash (<i>Fraxinus pennsylvanica</i>)	1	13	0	1	0	0	0	0	1	14
Apple species (<i>Malus</i> spp.)	4	2	0	0	0	0	0	0	4	2
Poplar species (<i>Populus</i> spp.)	1	0	1	0	0	0	0	0	2	0
Basswood (<i>Tilia americana</i>)	3	0	0	0	0	0	0	0	3	0
Total Number of Trees	108	36	35	3	15	1	8	2	166	42

P1585

Tree Size Class > Species	Polewood (10 - 24 cm DBH)		Small (26 - 36 cm DBH)		Medium (38 - 48 cm)		Large (50 cm +)		Total All Sizes	
	AGS	UGS	AGS	UGS	AGS	UGS	AGS	UGS	AGS	UGS
Willow species (<i>Salix</i> spp.)	1	0	0	0	0	0	0	0	1	0
Bur Oak (<i>Quercus macrocarpa</i>)	20	2	10	1	0	0	1	0	31	3
White Pine (<i>Pinus strobus</i>)	0	0	1	0	0	0	0	0	1	0
Apple species (<i>Malus</i> spp.)	0	1	0	1	0	0	0	0	0	2
Total Number of Trees	21	3	11	2	0	0	1	0	33	5

P1605

Tree Size Class > Species	Polewood (10 - 24 cm DBH)		Small (26 - 36 cm DBH)		Medium (38 - 48 cm)		Large (50 cm +)		Total All Sizes	
	AGS	UGS	AGS	UGS	AGS	UGS	AGS	UGS	AGS	UGS
Bur Oak (<i>Quercus macrocarpa</i>)	2	0	1	0	0	0	0	0	3	0
White Ash (<i>Fraxinus americana</i>)	2	6	0	0	0	0	0	0	2	6
Apple species (<i>Malus</i> spp.)	2	0	1	2	0	0	0	0	3	2
Green Ash (<i>Fraxinus pennsylvanica</i>)	0	16	0	3	0	0	0	0	0	19
Black Walnut (<i>Juglans nigra</i>)	1	0	0	0	0	0	0	0	1	0
Total Number of Trees	7	22	2	5	0	0	0	0	9	27

P1606

Tree Size Class > Species	Regeneration (<10 cm)		Polewood (10 - 24 cm DBH)		Small (26 - 36 cm DBH)		Medium (38 - 48 cm)		Large (50 cm +)		Total All Sizes	
	AGS	UGS	AGS	UGS	AGS	UGS	AGS	UGS	AGS	UGS	AGS	UGS
White Elm (<i>Ulmus americana</i>)	2	1	0	0	0	0	0	0	0	0	2	1
Green Ash (<i>Fraxinus pennsylvanica</i>)	1	5	0	0	0	0	0	0	0	0	1	0
White Ash (<i>Fraxinus americana</i>)	2	0	0	0	0	0	0	0	0	0	2	0
Total Number of Trees	5	6	0	0	0	0	0	0	0	0	5	1

P1607

Tree Size Class > Species	Regeneration (<10 cm)		Polewood (10 - 24 cm DBH)		Small (26 - 36 cm DBH)		Medium (38 - 48 cm)		Large (50 cm +)		Total All Sizes	
	AGS	UGS	AGS	UGS	AGS	UGS	AGS	UGS	AGS	UGS	AGS	UGS
Green Ash (<i>Fraxinus pennsylvanica</i>)	1	3	0	0	0	0	0	0	0	0	1	3
Total Number of Trees	1	3	0	0	0	0	0	0	0	0	1	3

P1614

Tree Size Class > Species	Polewood (10 - 24 cm DBH)		Small (26 - 36 cm DBH)		Medium (38 - 48 cm)		Large (50 cm +)		Total All Sizes	
	AGS	UGS	AGS	UGS	AGS	UGS	AGS	UGS	AGS	UGS
Silver Maple (<i>Acer saccharinum</i>)	0	0	1	5	4	1	5	0	10	6
Norway Spruce (<i>Picea abies</i>)	2	4	6	0	0	0	0	0	8	4
Eastern White Cedar (<i>Thuja occidentalis</i>)	2	0	0	0	0	0	0	0	2	0
Total Number of Trees	4	4	7	5	4	1	5	0	20	10

P1615

Tree Size Class > Species	Polewood (10 - 24 cm DBH)		Small (26 - 36 cm DBH)		Medium (38 - 48 cm)		Large (50 cm +)		Total All Sizes	
	AGS	UGS	AGS	UGS	AGS	UGS	AGS	UGS	AGS	UGS
Bur Oak (<i>Quercus macrocarpa</i>)	8	1	2	0	0	0	1	1	11	2
Silver Maple (<i>Acer saccharinum</i>)	0	0	1	0	0	0	1	0	2	0
Black Walnut (<i>Juglans nigra</i>)	20	0	1	0	1	0	1	0	23	0
White Elm (<i>Ulmus americana</i>)	1	0	0	0	0	0	0	0	1	0
Green Ash (<i>Fraxinus pennsylvanica</i>)	0	1	0	0	0	0	0	0	0	1
White Spruce (<i>Picea glauca</i>)	0	1	0	0	0	0	0	0	0	1
Willow species (<i>Salix</i> spp.)	0	0	0	0	0	0	0	1	0	1
Horsechestnut (<i>Aesculus hippocastanum</i>)	0	1	0	0	0	0	0	1	0	2
Total Number of Trees	29	4	4	0	1	0	3	3	37	7

P1616

Tree Size Class > Species	Polewood (10 - 24 cm DBH)		Small (26 - 36 cm DBH)		Medium (38 - 48 cm)		Large (50 cm +)		Total All Sizes	
	AGS	UGS	AGS	UGS	AGS	UGS	AGS	UGS	AGS	UGS
Black Locust (<i>Robinia pseudoacacia</i>)	1	0	1	0	1	0	0	0	3	0
Bur Oak (<i>Quercus macrocarpa</i>)	2	0	0	0	1	0	0	0	3	0
Silver Maple (<i>Acer saccharinum</i>)	0	0	0	0	0	1	0	0	0	1
Total Number of Trees	3	0	1	0	2	1	0	0	6	1

P1624

Tree Size Class > Species	Polewood (10 - 24 cm DBH)		Small (26 - 36 cm DBH)		Medium (38 - 48 cm)		Large (50 cm +)		Total All Sizes	
	AGS	UGS	AGS	UGS	AGS	UGS	AGS	UGS	AGS	UGS
Black Locust (<i>Robinia pseudoacacia</i>)	1	0	1	0	1	0	0	0	3	0
Silver Maple (<i>Acer saccharinum</i>)	0	0	0	1	0	0	0	1	0	2
Black Walnut (<i>Juglans nigra</i>)	1	0	1	0	1	1	1	1	4	2
Willow species (<i>Salix</i> spp.)	0	0	0	0	0	0	6	2	6	2
Total Number of Trees	2	0	2	1	2	1	7	4	13	6

P1631

Tree Size Class > Species	Polewood (10 - 24 cm DBH)		Small (26 - 36 cm DBH)		Medium (38 - 48 cm)		Large (50 cm +)		Total All Sizes	
	AGS	UGS	AGS	UGS	AGS	UGS	AGS	UGS	AGS	UGS
Basswood (<i>Tilia americana</i>)	1	0	0	0	0	0	0	0	1	0
Green Ash (<i>Fraxinus pennsylvanica</i>)	1	14	0	4	0	1	0	0	1	19
White Ash (<i>Fraxinus americana</i>)	1	5	1	2	0	0	0	0	2	7
Apple species (<i>Malus</i> spp.)	0	0	0	0	1	0	0	0	1	0
Bur Oak (<i>Quercus macrocarpa</i>)	14	0	3	0	1	0	0	0	18	0
White Elm (<i>Ulmus americana</i>)	1	1	0	0	0	0	0	0	1	1
Manitoba Maple (<i>Acer negundo</i>)	1	0	0	0	0	0	0	0	1	0
Black Walnut (<i>Juglans nigra</i>)	1	0	0	0	0	0	0	0	1	0
Total Number of Trees	20	20	4	6	2	1	0	0	26	27

P1633

Tree Size Class > Species	Polewood (10 - 24 cm DBH)		Small (26 - 36 cm DBH)		Medium (38 - 48 cm)		Large (50 cm +)		Total All Sizes	
	AGS	UGS	AGS	UGS	AGS	UGS	AGS	UGS	AGS	UGS
Bur Oak (<i>Quercus macrocarpa</i>)	40	5	20	6	8	0	7	2	75	13
White Elm (<i>Ulmus americana</i>)	3	1	0	1	0	0	0	0	3	2
Manitoba Maple (<i>Acer negundo</i>)	2	0	0	0	0	0	0	0	2	0
Shagbark Hickory (<i>Carya ovata</i>)	0	1	0	0	0	0	0	0	0	1
Black Walnut (<i>Juglans nigra</i>)	1	0	0	0	0	0	0	0	1	0
Apple species (<i>Malus</i> spp.)	1	1	2	0	0	0	0	0	3	1
Norway Maple (<i>Acer platanoides</i>)	1	0	0	0	0	0	0	0	1	0
Green Ash (<i>Fraxinus pennsylvanica</i>)	0	2	0	0	0	0	0	0	0	2
Silver Maple (<i>Acer saccharinum</i>)	0	0	0	0	0	0	0	1	0	1
Total Number of Trees	48	10	22	7	8	0	7	3	85	20

P1635

Tree Size Class > Species	Polewood (10 - 24 cm DBH)		Small (26 - 36 cm DBH)		Medium (38 - 48 cm)		Large (50 cm +)		Total All Sizes	
	AGS	UGS	AGS	UGS	AGS	UGS	AGS	UGS	AGS	UGS
Bur Oak (<i>Quercus macrocarpa</i>)	81	11	27	3	8	0	14	5	130	19
Apple species (<i>Malus</i> spp.)	7	5	0	2	2	0	0	0	9	7
Poplar species (<i>Populus</i> spp.)	3	1	0	0	0	0	0	0	3	1
Black Cherry (<i>Prunus serotina</i>)	1	0	0	0	0	0	0	0	1	0
Basswood (<i>Tilia americana</i>)	29	4	3	1	0	1	0	0	32	6
Silver Maple (<i>Acer saccharinum</i>)	10	1	2	0	0	1	2	0	14	2
Green Ash (<i>Fraxinus pennsylvanica</i>)	0	23	0	1	0	0	0	0	0	24
White Elm (<i>Ulmus americana</i>)	1	0	0	0	0	0	0	0	1	0
Shagbark Hickory (<i>Carya ovata</i>)	2	0	1	0	1	0	0	0	4	0
Pear species (<i>Pyrus</i> spp.)	0	0	1	0	0	0	0	0	1	0
Total Number of Trees	134	45	34	7	11	2	16	5	195	59

P1638

Tree Size Class > Species	Regeneration (<10 cm)		Polewood (10 - 24 cm DBH)		Small (26 - 36 cm DBH)		Medium (38 - 48 cm)		Large (50 cm +)		Total All Sizes	
	AGS	UGS	AGS	UGS	AGS	UGS	AGS	UGS	AGS	UGS	AGS	UGS
Apple species (<i>Malus</i> spp.)	2	0	0	0	0	0	0	0	0	0	2	0
Basswood (<i>Tilia americana</i>)	29	5	0	0	0	0	0	0	0	0	29	0
Sugar Maple (<i>Acer saccharum</i>)	15	0	0	0	0	0	0	0	0	0	15	0
Green Ash (<i>Fraxinus pennsylvanica</i>)	0	12	0	0	0	0	0	0	0	0	0	0
Total Number of Trees	46	17	0	0	0	0	0	0	0	0	46	0

TREE PROTECTION PLAN NOTES

- It is the applicants' responsibility to discuss potential impacts to trees located near or wholly on adjacent properties or on shared boundary lines with their neighbours. Should such trees be injured to the point of instability or death the applicant may be held responsible through civil action. The applicant would also be required to replace such trees to the satisfaction of Urban Forestry.
- Tree protection barriers shall be installed to standards as detailed in this document and to the satisfaction of Urban Forestry.
- Tree protection barriers must be installed using plywood clad hoarding (minimum 19mm or 3/4" thick) or an equivalent approved by Urban Forestry.
- Where required, signs as specified in Section 4, Tree Protection Signage must be attached to all sides of the barrier.
- Prior to the commencement of any site activity such as site alteration, demolition or construction, the tree protection measures specified on this plan must be installed to the satisfaction of Urban Forestry.
- Once all tree/site protection measures have been installed, Urban Forestry staff must be contacted to arrange for an inspection of the site and approval of the tree/site protection requirements. Photographs that clearly show the installed tree/site protection shall be provided for Urban Forestry review.
- Where changes to the location of the approved TPZ or sediment control or where temporary access to the TPZ is proposed, Urban Forestry must be contacted to obtain approval prior to alteration.
- Tree protection barriers must remain in place and in good condition during demolition, construction and/or site disturbance, including landscaping, and must not be altered, moved or removed until authorized by Urban Forestry.
- No construction activities including grade changes, surface treatments or excavation of any kind are permitted within the area identified on the Tree Protection Plan or Site Plan as a tree protection zone (TPZ). No root cutting is permitted. No storage of materials or fill is permitted within the TPZ. No movement or storage of vehicles or equipment is permitted within the TPZ. The area(s) identified as a TPZ must be protected and remain undisturbed at all times.
- All additional tree protection or preservation requirements, above and beyond the installation of tree protection barriers, must be undertaken or implemented as detailed in the Urban Forestry approved arborist report and/or the approved tree protection plan and to the satisfaction of Urban Forestry.
- If the minimum tree protection zone (TPZ) must be reduced to facilitate construction access, the tree protection barriers must be maintained at a lesser distance and the exposed portion of TPZ must be protected using a horizontal root protection method approved by Urban Forestry.
- Any roots or branches indicated on this plan which require pruning, as approved by Urban Forestry, must be pruned by an arborist. All pruning of tree roots and branches must be in accordance with good arboricultural practice. Roots that have received approval from Urban Forestry to be pruned must first be exposed using pneumatic (air) excavation, by hand digging or by a using low pressure hydraulic (water) excavation. The water pressure for hydraulic excavation must be low enough that root bark is not damaged or removed. This will allow a proper pruning cut and minimize tearing of the roots. The arborist retained to carry out crown or root pruning must contact Urban Forestry no less than three working days prior to conducting any specified work.
- The applicant/owner shall protect all by-law regulated trees in the area of consideration that have not been approved for removal throughout development works to the satisfaction of Urban Forestry.
- Convictions of offences respecting the regulations in the Street Tree By-law and Private Tree By-law are subject to fines. A person convicted of an offence under these by-laws is liable to a minimum fine of \$500 and a maximum fine of \$100,000 per tree, and/or a Special Fine of \$100,000. The landowner may be ordered by the City to stop the contravening activity or ordered to undertake work to correct the contravention.
- Prior to site disturbance the owner must confirm that no migratory birds are making use of the site for nesting. The owner must ensure that the works are in conformance with the Migratory Bird Convention Act and that no migratory bird nests will be impacted by the proposed work no less than 48 hours prior to conducting any specified work.

LEGEND

Tree Inventory

Refer to Table 1 and Table 2 of the report dated 06 April 2021 for complete tree inventory information. Trees greater than 10cm DBH on or within six meters of the subject properties and trees of all sizes on the City road right-of-way were included in the inventory.



Tree Removals

The removal of 123 trees and 16 tree polygons will be required to accommodate the proposed site plan. Trees identified for removal are indicated with RED ORANGE labels.

Tree Preservation


Preservation of 19 trees, three polygon features, and the existing woodlot will be possible with the appropriate tree protection measures. Trees identified for preservation are indicated with GREEN labels. Tree Preservation Zone (TPZ) circles represent minimum distances for construction and grading near trees respecting Milton Tree Protection Fencing Guidelines. Refer to the Tree Protection Plan Notes for preservation details.

- Tree Label (ORANGE) removal recommended due to poor condition
- Tree label (RED) removal required
- Surveyed tree location
- Tree Does Not Exist
- Property Boundary (DARK BLUE)
- Tree Preservation Fencing (THICK MAGENTA)
- Tree location identified by KFCI
- Tree Label (GREEN) preservation recommended
- Drip Line (MAGENTA Circle)



No.	Issue/Revisions	Date	By
1	Report Submission	28 Apr. '20	KD
2	Report Resubmission	04 May '20	KD
3	Report Resubmission	19 June '20	KD
4	Report Resubmission	05 Aug. '20	KD
5	Report Resubmission	10 Aug. '20	KD
6	Report Resubmission	06 Apr. '21	KD
7	Figure Resubmission	5 Aug. '21	CB

Base Data: David B. Searles Surveying Ltd. (topographic survey), TMIG (site plan)



KUNTZ FORESTRY CONSULTING Inc.
 146 Lakeshore Road West
 PO Box 1267 Lakeshore W PO
 Oakville ON L6K 0B3
 t: 289.537.1871
 e: consult@kuntzforestry.ca
 web: www.kuntzforestry.ca

Client
Studio TLA
 20 Champlain Blvd. | North York | Ontario | M3H 2Z1

Property
Milton Porta Lands
 Milton | Ontario

Existing Conditions, Proposed Site Plan,
 Tree Inventory & Preservation Plan

Project	P2375	Figure	1
Date	06 April 2021		
Scale	1:800		



TREE PROTECTION PLAN NOTES

- It is the applicants' responsibility to discuss potential impacts to trees located near or wholly on adjacent properties or on shared boundary lines with their neighbours. Should such trees be injured to the point of instability or death the applicant may be held responsible through civil action. The applicant would also be required to replace such trees to the satisfaction of Urban Forestry.
- Tree protection barriers shall be installed to standards as detailed in this document and to the satisfaction of Urban Forestry.
- Tree protection barriers must be installed using plywood clad hoarding (minimum 19mm or 3/4" thick) or an equivalent approved by Urban Forestry.
- Where required, signs as specified in Section 4, Tree Protection Signage must be attached to all sides of the barrier.
- Prior to the commencement of any site activity such as site alteration, demolition or construction, the tree protection measures specified on this plan must be installed to the satisfaction of Urban Forestry.
- Once all tree/site protection measures have been installed, Urban Forestry staff must be contacted to arrange for an inspection of the site and approval of the tree/site protection requirements. Photographs that clearly show the installed tree/site protection shall be provided for Urban Forestry review.
- Where changes to the location of the approved TPZ or sediment control or where temporary access to the TPZ is proposed, Urban Forestry must be contacted to obtain approval prior to alteration.
- Tree protection barriers must remain in place and in good condition during demolition, construction and/or site disturbance, including landscaping, and must not be altered, moved or removed until authorized by Urban Forestry.
- No construction activities including grade changes, surface treatments or excavation of any kind are permitted within the area identified on the Tree Protection Plan or Site Plan as a tree protection zone (TPZ). No root cutting is permitted. No storage of materials or fill is permitted within the TPZ. The area(s) identified as a TPZ must be protected and remain undisturbed at all times.
- All additional tree protection or preservation requirements, above and beyond the installation of tree protection barriers, must be undertaken or implemented as detailed in the Urban Forestry approved arborist report and/or the approved tree protection plan and to the satisfaction of Urban Forestry.
- If the minimum tree protection zone (TPZ) must be reduced to facilitate construction access, the tree protection barriers must be maintained at a lesser distance and the exposed portion of TPZ must be protected using a horizontal root protection method approved by Urban Forestry.
- Any roots or branches indicated on this plan which require pruning, as approved by Urban Forestry, must be pruned by an arborist. All pruning of tree roots and branches must be in accordance with good arboricultural practice. Roots that have received approval from Urban Forestry to be pruned must first be exposed using pneumatic (air) excavation, by hand digging or by a using low pressure hydraulic (water) excavation. The water pressure for hydraulic excavation must be low enough that root bark is not damaged or removed. This will allow a proper pruning cut and minimize tearing of the roots. The arborist retained to carry out crown or root pruning must contact Urban Forestry no less than three working days prior to conducting any specified work.
- The applicant/owner shall protect all by-law regulated trees in the area of consideration that have not been approved for removal throughout development works to the satisfaction of Urban Forestry.
- Convictions of offences respecting the regulations in the Street Tree By-law and Private Tree By-law are subject to fines. A person convicted of an offence under these by-laws is liable to a minimum fine of \$500 and a maximum fine of \$100,000 per tree, and/or a Special Fine of \$100,000. The landowner may be ordered by the City to stop the contravening activity or ordered to undertake work to correct the contravention.
- Prior to site disturbance the owner must confirm that no migratory birds are making use of the site for nesting. The owner must ensure that the works are in conformance with the Migratory Bird Convention Act and that no migratory bird nests will be impacted by the proposed work no less than 48 hours prior to conducting any specified work.

PROPOSED BUILDING
576,134 S.F.


PROPOSED BUILDING
384,481 S.F.

FUTURE OFFICE

FUTURE OFFICE




FUTURE OFFICE

FUTURE OFFICE



LEGEND

- Tree Inventory**
Refer to Table 1 and Table 2 of the report dated 06 April 2021 for complete tree inventory information. Trees greater than 10cm DBH on or within six meters of the subject properties and trees of all sizes on the City road right-of-way were included in the inventory.
- Tree Removals**
The removal of 123 trees and 16 tree polygons will be required to accommodate the proposed site plan. Trees identified for removal are indicated with RED ORANGE labels.
- Tree Preservation**
Preservation of 19 trees, three polygon features, and the existing woodlot will be possible with the appropriate tree protection measures. Trees identified for preservation are indicated with GREEN labels. Tree Preservation Zone (TPZ) circles represent minimum distances for construction and grading near trees respecting Milton Tree Protection Fencing Guidelines. Refer to the Tree Protection Plan Notes for preservation details.
- Tree Label (ORANGE) removal recommended due to poor condition
 - Tree label (RED) removal required
 - Surveyed tree location
 - Tree Does Not Exist
 - Property Boundary (DARK BLUE)
 - Tree Preservation Fencing (THICK MAGENTA)
 - Tree location identified by KFCI
 - Tree Label (GREEN) preservation recommended
 - Drip Line (MAGENTA Circle)



No.	Issue/Revisions	Date	By
1	Report Submission	28 Apr. '20	KD
2	Report Resubmission	04 May '20	KD
3	Report Resubmission	19 June '20	KD
4	Report Resubmission	05 Aug. '20	KD
5	Report Resubmission	10 Aug. '20	KD
6	Report Resubmission	06 Apr. '21	KD
7	Figure Resubmission	5 Aug. '21	CB

Base Data: David B. Searles Surveying Ltd. (topographic survey), TMIG (site plan)

KUNTZ FORESTRY CONSULTING Inc.
146 Lakeshore Road West
PO Box 1267 Lakeshore W PO
Oakville ON L6K 0B3
t: 289.537.1871
e: consult@kuntzforestry.ca
web: www.kuntzforestry.ca

Client
Studio TLA
20 Champlain Blvd. | North York | Ontario | M3H 2Z1

Property
Milton Porta Lands
Milton | Ontario




Existing Conditions, Proposed Site Plan, Tree Inventory & Preservation Plan

Project	P2375	Figure	2
Date	06 April 2021		
Scale	1:800		

- TREE PROTECTION PLAN NOTES**
- It is the applicants' responsibility to discuss potential impacts to trees located near or wholly on adjacent properties or on shared boundary lines with their neighbours. Should such trees be injured to the point of instability or death the applicant may be held responsible through civil action. The applicant would also be required to replace such trees to the satisfaction of Urban Forestry.
 - Tree protection barriers shall be installed to standards as detailed in this document and to the satisfaction of Urban Forestry.
 - Tree protection barriers must be installed using plywood clad hoarding (minimum 19mm or ¾" thick) or an equivalent approved by Urban Forestry.
 - Where required, signs as specified in Section 4, Tree Protection Signage must be attached to all sides of the barrier.
 - Prior to the commencement of any site activity such as site alteration, demolition or construction, the tree protection measures specified on this plan must be installed to the satisfaction of Urban Forestry.
 - Once all tree/site protection measures have been installed, Urban Forestry staff must be contacted to arrange for an inspection of the site and approval of the tree/site protection requirements. Photographs that clearly show the installed tree/site protection shall be provided for Urban Forestry review.
 - Where changes to the location of the approved TPZ or sediment control or where temporary access to the TPZ is proposed, Urban Forestry must be contacted to obtain approval prior to alteration.
 - Tree protection barriers must remain in place and in good condition during demolition, construction and/or site disturbance, including landscaping, and must not be altered, moved or removed until authorized by Urban Forestry.
 - No construction activities including grade changes, surface treatments or excavation of any kind are permitted within the area identified on the Tree Protection Plan or Site Plan as a tree protection zone (TPZ). No root cutting is permitted. No storage of materials or fill is permitted within the TPZ. No movement or storage of vehicles or equipment is permitted within the TPZ. The area(s) identified as a TPZ must be protected and remain undisturbed at all times.
 - All additional tree protection or preservation requirements, above and beyond the installation of tree protection barriers, must be undertaken or implemented as detailed in the Urban Forestry approved arborist report and/or the approved tree protection plan and to the satisfaction of Urban Forestry.
 - If the minimum tree protection zone (TPZ) must be reduced to facilitate construction access, the tree protection barriers must be maintained at a lesser distance and the exposed portion of TPZ must be protected using a horizontal root protection method approved by Urban Forestry.
 - Any roots or branches indicated on this plan which require pruning, as approved by Urban Forestry, must be pruned by an arborist. All pruning of tree roots and branches must be in accordance with good arboricultural practice. Roots that have received approval from Urban Forestry to be pruned must first be exposed using pneumatic (air) excavation, by hand digging or by a using low pressure hydraulic (water) excavation. The water pressure for hydraulic excavation must be low enough that root bark is not damaged or removed. This will allow a proper pruning cut and minimize tearing of the roots. The arborist retained to carry out crown or root pruning must contact Urban Forestry no less than three working days prior to conducting any specified work.
 - The applicant/owner shall protect all by-law regulated trees in the area of consideration that have not been approved for removal throughout development works to the satisfaction of Urban Forestry.
 - Convictions of offences respecting the regulations in the Street Tree By-law and Private Tree By-law are subject to fines. A person convicted of an offence under these by-laws is liable to a minimum fine of \$500 and a maximum fine of \$100,000 per tree, and/or a Special Fine of \$100,000. The landowner may be ordered by the City to stop the contravening activity or ordered to undertake work to correct the contravention.
 - Prior to site disturbance the owner must confirm that no migratory birds are making use of the site for nesting. The owner must ensure that the works are in conformance with the Migratory Bird Convention Act and that no migratory bird nests will be impacted by the proposed work no less than 48 hours prior to conducting any specified work.

LEGEND

- Tree Inventory**
- Refer to Table 1 and Table 2 of the report dated 06 April 2021 for complete tree inventory information. Trees greater than 10cm DBH on or within six metres of the subject properties and trees of all sizes on the City road right-of-way were included in the inventory.
- Tree Removals**
- The removal of 123 trees and 16 tree polygons will be required to accommodate the proposed site plan. Trees identified for removal are indicated with RED ORANGE labels.
- Tree Preservation**
- Preservation of 19 trees, three polygon features, and the existing woodlot will be possible with the appropriate tree protection measures. Trees identified for preservation are indicated with GREEN labels. Tree Preservation Zone (TPZ) circles represent minimum distances for construction and grading near trees respecting Milton Tree Protection Fencing Guidelines. Refer to the Tree Protection Plan Notes for preservation details.
- Tree Label (ORANGE) removal recommended due to poor condition
 - Tree label (RED) removal required
 - Surveyed tree location
 - Tree Does Not Exist
 - Property Boundary (DARK BLUE)
 - Tree Preservation Fencing (THICK MAGENTA)
 - Tree location identified by KFCI
 - Tree Label (GREEN) preservation recommended
 - Drip Line (MAGENTA Circle)



No.	Issue/Revisions	Date	By
1	Report Submission	28 Apr. '20	KD
2	Report Resubmission	04 May '20	KD
3	Report Resubmission	19 June '20	KD
4	Report Resubmission	05 Aug. '20	KD
5	Report Resubmission	10 Aug. '20	KD
6	Report Resubmission	06 Apr. '21	KD
7	Figure Resubmission	5 Aug. '21	CB

Base Data: David B. Searles Surveying Ltd. (topographic survey), TMIG (site plan)



KUNTZ FORESTRY CONSULTING Inc.
 146 Lakeshore Road West
 PO Box 1267 Lakeshore W PO
 Oakville ON L6K 0B3
 T: 289.837.1871
 e: consult@kuntzforestry.ca
 web: www.kuntzforestry.ca

Client
Studio TLA
 20 Champlain Blvd. | North York | Ontario | M3H 2Z1

Property
Milton Porta Lands
 Milton | Ontario

Existing Conditions, Proposed Site Plan,
 Tree Inventory & Preservation Plan

Project	P2375	Figure	3
Date	06 April 2021		
Scale	1:800		



LEGEND

Tree Inventory

Refer to Table 1 and Table 2 of the report dated 06 April 2021 for complete tree inventory information. Trees greater than 10cm DBH on or within six meters of the subject properties and trees of all sizes on the City road right-of-way were included in the inventory.




Tree Removals

The removal of 123 trees and 16 tree polygons will be required to accommodate the proposed site plan. Trees identified for removal are indicated with RED or ORANGE labels.

Tree Preservation

Preservation of 19 trees, three polygon features, and the existing woodlot will be possible with the appropriate tree protection measures. Trees identified for preservation are indicated with GREEN labels. Tree Preservation Zone (TPZ) circles represent minimum distances for construction and grading near trees respecting Milton Tree Protection Fencing Guidelines. Refer to the Tree Protection Plan Notes for preservation details.

- Tree Label (ORANGE) removal recommended due to poor condition
- Tree label (RED) removal required
- Surveyed tree location
- Tree Does Not Exist
- Property Boundary (DARK BLUE)
- Tree Preservation Fencing (THICK MAGENTA)
- Tree location identified by KFCI
- Tree Label (GREEN) preservation recommended
- Drip Line (MAGENTA Circle)



No.	Issue/Revisions	Date	By
1	Report Submission	28 Apr. '20	KD
2	Report Resubmission	04 May '20	KD
3	Report Resubmission	19 June '20	KD
4	Report Resubmission	05 Aug. '20	KD
5	Report Resubmission	10 Aug. '20	KD
6	Report Resubmission	06 Apr. '21	KD
7	Figure Resubmission	5 Aug. '21	CB

Base Data: David B. Searles Surveying Ltd. (topographic survey), TMIG (site plan)

KUNTZ FORESTRY CONSULTING Inc.
 146 Lakeshore Road West
 PO Box 1267 Lakeshore W PO
 Oakville ON L6K 0B3
 T: 289.537.1871
 E: consult@kuntzforestry.ca
 web: www.kuntzforestry.ca


Client
Studio TLA
 20 Champlain Blvd. | North York | Ontario | M3H 2Z1

Property
Milton Porta Lands
 Milton | Ontario

Existing Conditions, Proposed Site Plan, Tree Inventory & Preservation Plan

Project	P2375	Figure	4
Date	06 April 2021		
Scale	1:800		




- ### TREE PROTECTION PLAN NOTES
- It is the applicants' responsibility to discuss potential impacts to trees located near or wholly on adjacent properties or on shared boundary lines with their neighbours. Should such trees be injured to the point of instability or death the applicant may be held responsible through civil action. The applicant would also be required to replace such trees to the satisfaction of Urban Forestry.
 - Tree protection barriers shall be installed to standards as detailed in this document and to the satisfaction of Urban Forestry.
 - Tree protection barriers must be installed using plywood clad hoarding (minimum 19mm or ¾" thick) or an equivalent approved by Urban Forestry.
 - Where required, signs as specified in Section 4, Tree Protection Signage must be attached to all sides of the barrier.
 - Prior to the commencement of any site activity such as site alteration, demolition or construction, the tree protection measures specified on this plan must be installed to the satisfaction of Urban Forestry.
 - Once all trees/site protection measures have been installed, Urban Forestry staff must be contacted to arrange for an inspection of the site and approval of the trees/site protection requirements. Photographs that clearly show the installed trees/site protection shall be provided for Urban Forestry review.
 - Where changes to the location of the approved TPZ or sediment control or where temporary access to the TPZ is proposed, Urban Forestry must be contacted to obtain approval prior to alteration.
 - Tree protection barriers must remain in place and in good condition during demolition, construction and/or site disturbance, including landscaping, and must not be altered, moved or removed until authorized by Urban Forestry.
 - No construction activities including grade changes, surface treatments or excavation of any kind are permitted within the area identified on the Tree Protection Plan or Site Plan as a tree protection zone (TPZ). No root cutting is permitted. No storage of materials or fill is permitted within the TPZ. No movement or storage of vehicles or equipment is permitted within the TPZ. The area(s) identified as a TPZ must be protected and remain undisturbed at all times.
 - All additional tree protection or preservation requirements, above and beyond the installation of tree protection barriers, must be undertaken or implemented as detailed in the Urban Forestry approved arborist report and/or the approved tree protection plan and to the satisfaction of Urban Forestry.
 - If the minimum tree protection zone (TPZ) must be reduced to facilitate construction access, the tree protection barriers must be maintained at a lesser distance and the exposed portion of TPZ must be protected using a horizontal root protection method approved by Urban Forestry.
 - Any roots or branches indicated on this plan which require pruning, as approved by Urban Forestry, must be pruned by an arborist. All pruning of tree roots and branches must be in accordance with good arboricultural practice. Roots that have received approval from Urban Forestry to be pruned must first be exposed using pneumatic (air) excavation, by hand digging or by a using low pressure hydraulic (water) excavation. The water pressure for hydraulic excavation must be low enough that root bark is not damaged or removed. This will allow a proper pruning cut and minimize tearing of the roots. The arborist retained to carry out crown or root pruning must contact Urban Forestry no less than three working days prior to conducting any specified work.
 - The applicant/owner shall protect all by-law regulated trees in the area of consideration that have not been approved for removal throughout development works to the satisfaction of Urban Forestry.
 - Convictions of offences respecting the regulations in the Street Tree By-law and Private Tree By-law are subject to fines. A person convicted of an offence under these by-laws is liable to a minimum fine of \$500 and a maximum fine of \$100,000 per tree, and/or a Special Fine of \$100,000. The landowner may be ordered by the City to stop the contravening activity or ordered to undertake work to correct the contravention.
 - Prior to site disturbance the owner must confirm that no migratory birds are making use of the site for nesting. The owner must ensure that the works are in conformance with the Migratory Bird Convention Act and that no migratory bird nests will be impacted by the proposed work no less than 48 hours prior to conducting any specified work.



- TREE PROTECTION PLAN NOTES**
- It is the applicants' responsibility to discuss potential impacts to trees located near or wholly on adjacent properties or on shared boundary lines with their neighbours. Should such trees be injured to the point of instability or death the applicant may be held responsible through civil action. The applicant would also be required to replace such trees to the satisfaction of Urban Forestry.
 - Tree protection barriers shall be installed to standards as detailed in this document and to the satisfaction of Urban Forestry.
 - Tree protection barriers must be installed using plywood clad hoarding (minimum 19mm or ¾" thick) or an equivalent approved by Urban Forestry.
 - Where required, signs as specified in Section 4, Tree Protection Signage must be attached to all sides of the barrier.
 - Prior to the commencement of any site activity such as site alteration, demolition or construction, the tree protection measures specified on this plan must be installed to the satisfaction of Urban Forestry.
 - Once all tree/site protection measures have been installed, Urban Forestry staff must be contacted to arrange for an inspection of the site and approval of the tree/site protection requirements. Photographs that clearly show the installed tree/site protection shall be provided for Urban Forestry review.
 - Where changes to the location of the approved TPZ or sediment control or where temporary access to the TPZ is proposed, Urban Forestry must be contacted to obtain approval prior to alteration.
 - Tree protection barriers must remain in place and in good condition during demolition, construction and/or site disturbance, including landscaping, and must not be altered, moved or removed until authorized by Urban Forestry.
 - No construction activities including grade changes, surface treatments or excavation of any kind are permitted within the area identified on the Tree Protection Plan or Site Plan as a tree protection zone (TPZ). No root cutting is permitted. No storage of materials or fill is permitted within the TPZ. No movement or storage of vehicles or equipment is permitted within the TPZ. The area(s) identified as a TPZ must be protected and remain undisturbed at all times.
 - All additional tree protection or preservation requirements, above and beyond the installation of tree protection barriers, must be undertaken or implemented as detailed in the Urban Forestry approved arborist report and/or the approved tree protection plan and to the satisfaction of Urban Forestry.
 - If the minimum tree protection zone (TPZ) must be reduced to facilitate construction access, the tree protection barriers must be maintained at a lesser distance and the exposed portion of TPZ must be protected using a horizontal root protection method approved by Urban Forestry.
 - Any roots or branches indicated on this plan which require pruning, as approved by Urban Forestry, must be pruned by an arborist. All pruning of tree roots and branches must be in accordance with good arboricultural practice. Roots that have received approval from Urban Forestry to be pruned must first be exposed using pneumatic (air) excavation, by hand digging or by a using low pressure hydraulic (water) excavation. The water pressure for hydraulic excavation must be low enough that root bark is not damaged or removed. This will allow a proper pruning cut and minimize tearing of the roots. The arborist retained to carry out crown or root pruning must contact Urban Forestry no less than three working days prior to conducting any specified work.
 - The applicant/owner shall protect all by-law regulated trees in the area of consideration that have not been approved for removal throughout development works to the satisfaction of Urban Forestry.
 - Convictions of offences respecting the regulations in the Street Tree By-law and Private Tree By-law are subject to fines. A person convicted of an offence under these by-laws is liable to a minimum fine of \$500 and a maximum fine of \$100,000 per tree, and/or a Special Fine of \$100,000. The landowner may be ordered by the City to stop the contravening activity or ordered to undertake work to correct the contravention.
 - Prior to site disturbance the owner must confirm that no migratory birds are making use of the site for nesting. The owner must ensure that the works are in conformance with the Migratory Bird Convention Act and that no migratory bird nests will be impacted by the proposed work no less than 48 hours prior to conducting any specified work.

LEGEND

- Tree Inventory**
Refer to Table 1 and Table 2 of the report dated 06 April 2021 for complete tree inventory information. Trees greater than 10cm DBH on or within six meters of the subject properties and trees of all sizes on the City road right-of-way were included in the inventory.
- Tree Removals**
The removal of 123 trees and 16 tree polygons will be required to accommodate the proposed site plan. Trees identified for removal are indicated with RED ORANGE labels.
- Tree Preservation**
Preservation of 19 trees, three polygon features, and the existing woodlot will be possible with the appropriate tree protection measures. Trees identified for preservation are indicated with GREEN labels. Tree Preservation Zone (TPZ) circles represent minimum distances for construction and grading near trees respecting Milton Tree Protection Fencing Guidelines. Refer to the Tree Protection Plan Notes for preservation details.
- Tree Label (ORANGE) removal recommended due to poor condition
 - Tree label (RED) removal required
 - Surveyed tree location
 - Tree Does Not Exist
 - Property Boundary (DARK BLUE)
 - Tree Preservation Fencing (THICK MAGENTA)
 - Tree location identified by KFCI
 - Tree Label (GREEN) preservation recommended
 - Drip Line (MAGENTA Circle)



No.	Issue/Revisions	Date	By
1	Report Submission	28 Apr '20	KD
2	Report Resubmission	04 May '20	KD
3	Report Resubmission	19 June '20	KD
4	Report Resubmission	05 Aug. '20	KD
5	Report Resubmission	10 Aug. '20	KD
6	Report Resubmission	06 Apr. '21	KD
7	Figure Resubmission	5 Aug. '21	CB

Base Data: David B. Searles Surveying Ltd. (topographic survey), TMIG (site plan)


KUNTZ FORESTRY CONSULTING Inc.
146 Lakeshore Road West
PO Box 1267 Lakeshore W PO
Oakville ON L6K 0B3
t: 289.537.1871
e: consult@kuntzforestry.ca
web: www.kuntzforestry.ca

Client
Studio TLA
20 Champlain Blvd. | North York | Ontario | M3H 2Z1

Property
Milton Porta Lands
Milton | Ontario

Existing Conditions, Proposed Site Plan,
Tree Inventory & Preservation Plan

Project	P2375	Figure 5
Date	06 April 2021	
Scale	1:800	



LEGEND

Tree Inventory

Refer to Table 1 and Table 2 of the report dated 06 April 2021 for complete tree inventory information. Trees greater than 10cm DBH on or within six meters of the subject properties and trees of all sizes on the City road right-of-way were included in the inventory.




Tree Removals

The removal of 123 trees and 16 tree polygons will be required to accommodate the proposed site plan. Trees identified for removal are indicated with RED ORANGE labels.

Tree Preservation

Preservation of 19 trees, three polygon features, and the existing woodlot will be possible with the appropriate tree protection measures. Trees identified for preservation are indicated with GREEN labels. Tree Preservation Zone (TPZ) circles represent minimum distances for construction and grading near trees respecting Milton Tree Protection Fencing Guidelines. Refer to the Tree Protection Plan Notes for preservation details.

- Tree Label (ORANGE) removal recommended due to poor condition
- Tree label (RED) removal required
- Surveyed tree location
- Tree Does Not Exist
- Property Boundary (DARK BLUE)
- Tree Preservation Fencing (THICK MAGENTA)
- Tree location identified by KFCI
- Tree Label (GREEN) preservation recommended
- Drip Line (MAGENTA Circle)

No.	Issue/Revisions	Date	By
1	Report Submission	28 Apr '20	KD
2	Report Resubmission	04 May '20	KD
3	Report Resubmission	19 June '20	KD
4	Report Resubmission	05 Aug '20	KD
5	Report Resubmission	10 Aug '20	KD
6	Report Resubmission	06 Apr '21	KD
7	Figure Resubmission	5 Aug '21	CB

Base Data: David B. Searles Surveying Ltd. (topographic survey), TMIG (site plan)



KUNTZ FORESTRY CONSULTING Inc.
 146 Lakeshore Road West
 PO Box 1267 Lakeshore W PO
 Oakville ON L6K 0B3
 T: 289.537.1871
 e: consult@kuntzforestry.ca
 web: www.kuntzforestry.ca


Client
Studio TLA
 20 Champlain Blvd. | North York | Ontario | M3H 2Z1

Property
Milton Porta Lands
 Milton | Ontario

Existing Conditions, Proposed Site Plan,
 Tree Inventory & Preservation Plan

Project	P2375	Figure 6
Date	06 April 2021	
Scale	1:800	




- ### TREE PROTECTION PLAN NOTES
- It is the applicants' responsibility to discuss potential impacts to trees located near or wholly on adjacent properties or on shared boundary lines with their neighbours. Should such trees be injured to the point of instability or death the applicant may be held responsible through civil action. The applicant would also be required to replace such trees to the satisfaction of Urban Forestry.
 - Tree protection barriers shall be installed to standards as detailed in this document and to the satisfaction of Urban Forestry.
 - Tree protection barriers must be installed using plywood clad hoarding (minimum 19mm or ¾" thick) or an equivalent approved by Urban Forestry.
 - Where required, signs as specified in Section 4, Tree Protection Signage must be attached to all sides of the barrier.
 - Prior to the commencement of any site activity such as site alteration, demolition or construction, the tree protection measures specified on this plan must be installed to the satisfaction of Urban Forestry.
 - Once all trees/site protection measures have been installed, Urban Forestry staff must be contacted to arrange for an inspection of the site and approval of the trees/site protection requirements. Photographs that clearly show the installed trees/site protection shall be provided for Urban Forestry review.
 - Where changes to the location of the approved TPZ or sediment control or where temporary access to the TPZ is proposed, Urban Forestry must be contacted to obtain approval prior to alteration.
 - Tree protection barriers must remain in place and in good condition during demolition, construction and/or site disturbance, including landscaping, and must not be altered, moved or removed until authorized by Urban Forestry.
 - No construction activities including grade changes, surface treatments or excavation of any kind are permitted within the area identified on the Tree Protection Plan or Site Plan as a tree protection zone (TPZ). No root cutting is permitted. No storage of materials or fill is permitted within the TPZ. No movement or storage of vehicles or equipment is permitted within the TPZ. The area(s) identified as a TPZ must be protected and remain undisturbed at all times.
 - All additional tree protection or preservation requirements, above and beyond the installation of tree protection barriers, must be undertaken or implemented as detailed in the Urban Forestry approved arborist report and/or the approved tree protection plan and to the satisfaction of Urban Forestry.
 - If the minimum tree protection zone (TPZ) must be reduced to facilitate construction access, the tree protection barriers must be maintained at a lesser distance and the exposed portion of TPZ must be protected using a horizontal root protection method approved by Urban Forestry.
 - Any roots or branches indicated on this plan which require pruning, as approved by Urban Forestry, must be pruned by an arborist. All pruning of tree roots and branches must be in accordance with good arboricultural practice. Roots that have received approval from Urban Forestry to be pruned must first be exposed using pneumatic (air) excavation, by hand digging or by a using low pressure hydraulic (water) excavation. The water pressure for hydraulic excavation must be low enough that root bark is not damaged or removed. This will allow a proper pruning cut and minimize tearing of the roots. The arborist retained to carry out crown or root pruning must contact Urban Forestry no less than three working days prior to conducting any specified work.
 - The applicant/owner shall protect all by-law regulated trees in the area of consideration that have not been approved for removal throughout development works to the satisfaction of Urban Forestry.
 - Convictions of offences respecting the regulations in the Street Tree By-law and Private Tree By-law are subject to fines. A person convicted of an offence under these by-laws is liable to a minimum fine of \$500 and a maximum fine of \$100,000 per tree, and/or a Special Fine of \$100,000. The landowner may be ordered by the City to stop the contravening activity or ordered to undertake work to correct the contravention.
 - Prior to site disturbance the owner must confirm that no migratory birds are making use of the site for nesting. The owner must ensure that the works are in conformance with the Migratory Bird Convention Act and that no migratory bird nests will be impacted by the proposed work no less than 48 hours prior to conducting any specified work.



- TREE PROTECTION PLAN NOTES**
- It is the applicants' responsibility to discuss potential impacts to trees located near or wholly on adjacent properties or on shared boundary lines with their neighbours. Should such trees be injured to the point of instability or death the applicant may be held responsible through civil action. The applicant would also be required to replace such trees to the satisfaction of Urban Forestry.
 - Tree protection barriers shall be installed to standards as detailed in this document and to the satisfaction of Urban Forestry.
 - Tree protection barriers must be installed using plywood clad hoarding (minimum 19mm or ¾" thick) or an equivalent approved by Urban Forestry.
 - Where required, signs as specified in Section 4, Tree Protection Signage must be attached to all sides of the barrier.
 - Prior to the commencement of any site activity such as site alteration, demolition or construction, the tree protection measures specified on this plan must be installed to the satisfaction of Urban Forestry.
 - Once all tree/site protection measures have been installed, Urban Forestry staff must be contacted to arrange for an inspection of the site and approval of the tree/site protection requirements. Photographs that clearly show the installed tree/site protection shall be provided for Urban Forestry review.
 - Where changes to the location of the approved TPZ or sediment control or where temporary access to the TPZ is proposed, Urban Forestry must be contacted to obtain approval prior to alteration.
 - Tree protection barriers must remain in place and in good condition during demolition, construction and/or site disturbance, including landscaping, and must not be altered, moved or removed until authorized by Urban Forestry.
 - No construction activities including grade changes, surface treatments or excavation of any kind are permitted within the area identified on the Tree Protection Plan or Site Plan as a tree protection zone (TPZ). No root cutting is permitted. No storage of materials or fill is permitted within the TPZ. The area(s) identified as a TPZ must be protected and remain undisturbed at all times.
 - All additional tree protection or preservation requirements, above and beyond the installation of tree protection barriers, must be undertaken or implemented as detailed in the Urban Forestry approved arborist report and/or the approved tree protection plan and to the satisfaction of Urban Forestry.
 - If the minimum tree protection zone (TPZ) must be reduced to facilitate construction access, the tree protection barriers must be maintained at a lesser distance and the exposed portion of TPZ must be protected using a horizontal root protection method approved by Urban Forestry.
 - Any roots or branches indicated on this plan which require pruning, as approved by Urban Forestry, must be pruned by an arborist. All pruning of tree roots and branches must be in accordance with good arboricultural practice. Roots that have received approval from Urban Forestry to be pruned must first be exposed using pneumatic (air) excavation, by hand digging or by a using low pressure hydraulic (water) excavation. The water pressure for hydraulic excavation must be low enough that root bark is not damaged or removed. This will allow a proper pruning cut and minimize tearing of the roots. The arborist retained to carry out crown or root pruning must contact Urban Forestry no less than three working days prior to conducting any specified work.
 - The applicant/owner shall protect all by-law regulated trees in the area of consideration that have not been approved for removal throughout development works to the satisfaction of Urban Forestry.
 - Convictions of offences respecting the regulations in the Street Tree By-law and Private Tree By-law are subject to fines. A person convicted of an offence under these by-laws is liable to a minimum fine of \$500 and a maximum fine of \$100,000 per tree, and/or a Special Fine of \$100,000. The landowner may be ordered by the City to stop the contravening activity or ordered to undertake work to correct the contravention.
 - Prior to site disturbance the owner must confirm that no migratory birds are making use of the site for nesting. The owner must ensure that the works are in conformance with the Migratory Bird Convention Act and that no migratory bird nests will be impacted by the proposed work no less than 48 hours prior to conducting any specified work.

LEGEND

- Tree Inventory**
Refer to Table 1 and Table 2 of the report dated 06 April 2021 for complete tree inventory information. Trees greater than 10cm DBH on or within six meters of the subject properties and trees of all sizes on the City road right-of-way were included in the inventory.
- Tree Removals**
The removal of 123 trees and 16 tree polygons will be required to accommodate the proposed site plan. Trees identified for removal are indicated with RED ORANGE labels.
- Tree Preservation**
Preservation of 19 trees, three polygon features, and the existing woodlot will be possible with the appropriate tree protection measures. Trees identified for preservation are indicated with GREEN labels. Tree Preservation Zone (TPZ) circles represent minimum distances for construction and grading near trees respecting Milton Tree Protection Fencing Guidelines. Refer to the Tree Protection Plan Notes for preservation details.
- Tree Label (ORANGE) removal recommended due to poor condition
 - Tree label (RED) removal required
 - Surveyed tree location
 - Tree Does Not Exist
 - Property Boundary (DARK BLUE)
 - Tree Preservation Fencing (THICK MAGENTA)
 - Tree location identified by KFCI
 - Tree Label (GREEN) preservation recommended
 - Drip Line (MAGENTA Circle)



No.	Issue/Revisions	Date	By
1	Report Submission	28 Apr '20	KD
2	Report Resubmission	04 May '20	KD
3	Report Resubmission	19 June '20	KD
4	Report Resubmission	05 Aug '20	KD
5	Report Resubmission	10 Aug '20	KD
6	Report Resubmission	06 Apr '21	KD
7	Figure Resubmission	5 Aug '21	CB

Base Data: David B. Searles Surveying Ltd. (topographic survey), TMIG (site plan)


KUNTZ FORESTRY CONSULTING Inc.
146 Lakeshore Road West
PO Box 1267 Lakeshore W PO
Oakville ON L6K 0B3
T: 289.537.1871
E: consult@kuntzforestry.ca
Web: www.kuntzforestry.ca

Client
Studio TLA
20 Champlain Blvd. | North York | Ontario | M3H 2Z1

Property
Milton Porta Lands
Milton | Ontario


Existing Conditions, Proposed Site Plan,
Tree Inventory & Preservation Plan

Project	P2375	Figure	7
Date	06 April 2021		
Scale	1:800		



TREE PROTECTION PLAN NOTES

- It is the applicants' responsibility to discuss potential impacts to trees located near or wholly on adjacent properties or on shared boundary lines with their neighbours. Should such trees be injured to the point of instability or death the applicant may be held responsible through civil action. The applicant would also be required to replace such trees to the satisfaction of Urban Forestry.
- Tree protection barriers shall be installed to standards as detailed in this document and to the satisfaction of Urban Forestry.
- Tree protection barriers must be installed using plywood clad hoarding (minimum 19mm or ¾" thick) or an equivalent approved by Urban Forestry.
- Where required, signs as specified in Section 4, Tree Protection Signage must be attached to all sides of the barrier.
- Prior to the commencement of any site activity such as site alteration, demolition or construction, the tree protection measures specified on this plan must be installed to the satisfaction of Urban Forestry.
- Once all tree/site protection measures have been installed, Urban Forestry staff must be contacted to arrange for an inspection of the site and approval of the tree/site protection requirements. Photographs that clearly show the installed tree/site protection shall be provided for Urban Forestry review.
- Where changes to the location of the approved TPZ or sediment control or where temporary access to the TPZ is proposed, Urban Forestry must be contacted to obtain approval prior to alteration.
- Tree protection barriers must remain in place and in good condition during demolition, construction and/or site disturbance, including landscaping, and must not be altered, moved or removed until authorized by Urban Forestry.
- No construction activities including grade changes, surface treatments or excavation of any kind are permitted within the area identified on the Tree Protection Plan or Site Plan as a tree protection zone (TPZ). No root cutting is permitted. No storage of materials or fill is permitted within the TPZ. The area(s) identified as a TPZ must be protected and remain undisturbed at all times.
- All additional tree protection or preservation requirements, above and beyond the installation of tree protection barriers, must be undertaken or implemented as detailed in the Urban Forestry approved arborist report and/or the approved tree protection plan and to the satisfaction of Urban Forestry.
- If the minimum tree protection zone (TPZ) must be reduced to facilitate construction access, the tree protection barriers must be maintained at a lesser distance and the exposed portion of TPZ must be protected using a horizontal root protection method approved by Urban Forestry.
- Any roots or branches indicated on this plan which require pruning, as approved by Urban Forestry, must be pruned by an arborist. All pruning of tree roots and branches must be in accordance with good arboricultural practice. Roots that have received approval from Urban Forestry to be pruned must first be exposed using pneumatic (air) excavation, by hand digging or by a using low pressure hydraulic (water) excavation. The water pressure for hydraulic excavation must be low enough that root bark is not damaged or removed. This will allow a proper pruning cut and minimize tearing of the roots. The arborist retained to carry out crown or root pruning must contact Urban Forestry no less than three working days prior to conducting any specified work.
- The applicant/owner shall protect all by-law regulated trees in the area of consideration that have not been approved for removal throughout development works to the satisfaction of Urban Forestry.
- Convictions of offences respecting the regulations in the Street Tree By-law and Private Tree By-law are subject to fines. A person convicted of an offence under these by-laws is liable to a minimum fine of \$500 and a maximum fine of \$100,000 per tree, and/or a Special Fine of \$100,000. The landowner may be ordered by the City to stop the contravening activity or ordered to undertake work to correct the contravention.
- Prior to site disturbance the owner must confirm that no migratory birds are making use of the site for nesting. The owner must ensure that the works are in conformance with the Migratory Bird Convention Act and that no migratory bird nests will be impacted by the proposed work no less than 48 hours prior to conducting any specified work.



LEGEND

Tree Inventory

Refer to Table 1 and Table 2 of the report dated 06 April 2021 for complete tree inventory information. Trees greater than 10cm DBH on or within six metres of the subject properties and trees of all sizes on the City road right-of-way were included in the inventory.



Tree Removals

The removal of 123 trees and 16 tree polygons will be required to accommodate the proposed site plan. Trees identified for removal are indicated with RED ORANGE labels.

Tree Preservation

Preservation of 19 trees, three polygon features, and the existing woodlot will be possible with the appropriate tree protection measures. Trees identified for preservation are indicated with GREEN labels. Tree Preservation Zone (TPZ) circles represent minimum distances for construction and grading near trees respecting Milton Tree Protection Fencing Guidelines. Refer to the Tree Protection Plan Notes for preservation details.

Tree Label (ORANGE) removal recommended due to poor condition	
Tree label (RED) removal required	
Surveyed tree location	
Tree Does Not Exist	
Property Boundary (DARK BLUE)	
Tree Preservation Fencing (THICK MAGENTA)	
Tree location identified by KFCI	
Tree Label (GREEN) preservation recommended	
Drip Line (MAGENTA Circle)	



No.	Issue/Revisions	Date	By
1	Report Submission	28 Apr. '20	KD
2	Report Resubmission	04 May '20	KD
3	Report Resubmission	19 June '20	KD
4	Report Resubmission	05 Aug. '20	KD
5	Report Resubmission	10 Aug. '20	KD
6	Report Resubmission	06 Apr. '21	KD
7	Figure Resubmission	5 Aug. '21	CB

Base Data: David B. Searles Surveying Ltd. (topographic survey), TMIG (site plan)

KUNTZ FORESTRY CONSULTING Inc.

146 Lakeshore Road West
PO Box 1267 Lakeshore W PO
Oakville ON L6K 0B3
t: 289.537.1871
e: consult@kuntzforestry.ca
web: www.kuntzforestry.ca

Client
Studio TLA
20 Champlain Blvd. | North York | Ontario | M3H 2Z1

Property
Milton Porta Lands
Milton | Ontario

Existing Conditions, Proposed Site Plan, Tree Inventory & Preservation Plan

Project	P2375	8
Date	06 April 2021	
Scale	1:800	

LEGEND

Tree Inventory




Refer to Table 1 and Table 2 of the report dated 06 April 2021 for complete tree inventory information. Trees greater than 10cm DBH on or within six meters of the subject properties and trees of all sizes on the City road right-of-way were included in the inventory.

Tree Removals

The removal of 123 trees and 16 tree polygons will be required to accommodate the proposed site plan. Trees identified for removal are indicated with RED or ORANGE labels.

Tree Preservation

Preservation of 19 trees, three polygon features, and the existing woodlot will be possible with the appropriate tree protection measures. Trees identified for preservation are indicated with GREEN labels. Tree Preservation Zone (TPZ) circles represent minimum distances for construction and grading near trees respecting Milton Tree Protection Fencing Guidelines. Refer to the Tree Protection Plan Notes for preservation details.



- TREE PROTECTION PLAN NOTES**
- It is the applicant's responsibility to discuss potential impacts to trees located near or wholly on adjacent properties or on shared boundary lines with their neighbours. Should such trees be injured to the point of instability or death the applicant may be held responsible through civil action. The applicant would also be required to replace such trees to the satisfaction of Urban Forestry.
 - Tree protection barriers shall be installed to standards as detailed in this document and to the satisfaction of Urban Forestry.
 - Tree protection barriers must be installed using plywood clad hoarding (minimum 19mm or 3/4" thick) or an equivalent approved by Urban Forestry.
 - Where required, signs as specified in Section 4, Tree Protection Signage must be attached to all sides of the barrier.
 - Prior to the commencement of any site activity such as site alteration, demolition or construction, the tree protection measures specified on this plan must be installed to the satisfaction of Urban Forestry.
 - Once all tree/site protection measures have been installed, Urban Forestry staff must be contacted to arrange for an inspection of the site and approval of the tree/site protection requirements. Photographs that clearly show the installed tree/site protection shall be provided for Urban Forestry review.
 - Where changes to the location of the approved TPZ or sediment control or where temporary access to the TPZ is proposed, Urban Forestry must be contacted to obtain approval prior to alteration.
 - Tree protection barriers must remain in place and in good condition during demolition, construction and/or site disturbance, including landscaping, and must not be altered, moved or removed until authorized by Urban Forestry.
 - No construction activities including grade changes, surface treatments or excavation of any kind are permitted within the area identified on the Tree Protection Plan or Site Plan as a tree protection zone (TPZ). No root cutting is permitted. No storage of materials or fill is permitted within the TPZ. No movement or storage of vehicles or equipment is permitted within the TPZ. The area(s) identified as a TPZ must be protected and remain undisturbed at all times.
 - All additional tree protection or preservation requirements, above and beyond the installation of tree protection barriers, must be undertaken or implemented as detailed in the Urban Forestry approved arborist report and/or the approved tree protection plan and to the satisfaction of Urban Forestry.
 - If the minimum tree protection zone (TPZ) must be reduced to facilitate construction access, the tree protection barriers must be maintained at a lesser distance and the exposed portion of TPZ must be protected using a horizontal root protection method approved by Urban Forestry.
 - Any roots or branches indicated on this plan which require pruning, as approved by Urban Forestry, must be pruned by an arborist. All pruning of tree roots and branches must be in accordance with good arboricultural practice. Roots that have received approval from Urban Forestry to be pruned must first be exposed using pneumatic (air) excavation, by hand digging or by a using low pressure hydraulic (water) excavation. The water pressure for hydraulic excavation must be low enough that root bark is not damaged or removed. This will allow a proper pruning cut and minimize bearing of the roots. The arborist retained to carry out crown or root pruning must contact Urban Forestry no less than three working days prior to conducting any specified work.
 - The applicant/owner shall protect all by-law regulated trees in the area of consideration that have not been approved for removal throughout development works to the satisfaction of Urban Forestry.
 - Convictions of offences respecting the regulations in the Street Tree By-law and Private Tree By-law are subject to fines. A person convicted of an offence under these by-laws is liable to a minimum fine of \$500 and a maximum fine of \$100,000 per tree, and/or a Special Fine of \$100,000. The landowner may be ordered by the City to stop the contravening activity or ordered to undertake work to correct the contravention.
 - Prior to site disturbance the owner must confirm that no migratory birds are making use of the site for nesting. The owner must ensure that the works are in conformance with the Migratory Bird Convention Act and that no migratory bird nests will be impacted by the proposed work no less than 48 hours prior to conducting any specified work.

No.	Issue/Revisions	Date	By
1	Report Submission	28 Apr. '20	KD
2	Report Resubmission	04 May '20	KD
3	Report Resubmission	19 June '20	KD
4	Report Resubmission	05 Aug. '20	KD
5	Report Resubmission	10 Aug. '20	KD
6	Report Resubmission	06 Apr. '21	KD
7	Figure Resubmission	5 Aug. '21	CB

Base Data: David B. Searles Surveying Ltd. (topographic survey), TMIG (site plan)

KUNTZ FORESTRY CONSULTING Inc.
 146 Lakeshore Road West
 PO Box 1267 Lakeshore W PO
 Oakville ON L6K 0B3
 T: 289.837.1871
 E: consult@kuntzforestry.ca
 web: www.kuntzforestry.ca

Client
Studio TLA
 20 Champlain Blvd. | North York | Ontario | M3H 2Z1

Property
Milton Porta Lands
 Milton | Ontario

Existing Conditions, Proposed Site Plan, Tree Inventory & Preservation Plan

Project	P2375	Figure	9
Date	06 April 2021		
Scale	1:3000		